



# केन्द्रीय रेशम जननद्रव्य संसाधन केन्द्र

केन्द्रीय रेशम बोर्ड, वस्त्र मंत्रालय - भारत सरकार

राष्ट्रीय सक्रिय जननद्रव्य स्थल (एन.बी.पी.जी.आर., नई दिल्ली द्वारा मान्यताप्राप्त)

## Central Sericultural Germplasm Resources Centre

Central Silk Board, Ministry of Textiles - Govt. of India

National Active Germplasm Site (Recognized by NBPGR, New Delhi)

No. CSB/GRC/3(22)/2013/Stores/

Date: 04<sup>th</sup> September, 2014

### TENDER NOTIFICATION

Sub:- Inviting competitive rate quotations for Instalation of **1 No. 30 KVA Diesel Generator Set** at CSGRC, CSB, Hosur - reg.

This Centre has purchased 1 No. 30 KVA Diesel Generator Set as per the specification given below. Quatations are invited from Electrical Licenced Contractors for installation of the DG set, in CSGRC premises, in the enclosed Proforma duly indicating the discount to be allowed on quoted value and Taxes, if any. The quotation should be inclusive of **cost of materials and labour charges** for the said installation.

#### Specification of 30 KVA Diesel Genarator set - Make and Model :- Kirloskar - KG35AS :-

<u>Engine:-</u>	KVA :30, RPM:1500, Cooling: Liquid, Fuel: Diesel Run
<u>Alternator:-</u>	PF:0.8, Hertz: 50 HZ, Volts: 415, Phase: 3
<u>Accessories:-</u>	Battery: 88 AH, Fuel Tank: 100 Ltrs., Silencer: Residential, C. Panel: Std. panel (manual operation)
<u>Acoustic:-</u>	CPCB Approved enclosure Size (mm): L 2530 x W 1190 x H 2100
<u>Make</u>	Kirloskar Green


Quotation should be sent to the undersigned in a **sealed envelope super scribing as "QUOTATION FOR INSTALLATION OF 1 No. 30 KVA DIESEL GENERATOR SET"**, so as to reach this office on or before **15th Sept., 2014 at 3.00 p.m.** The quotations received after the due date and time of receipt will be rejected. The Quotations will be opened by a Committee on the **same day at 3.30 p.m.**

The undersigned reserves the right to accept or reject any or all quotations without assigning any reason whatsoever.

The Terms and Conditions are as under:-

- (1) **Validity : Rate quoted should be valid for 90 days.**
- (2) Instalation : Within 15 days from the date of receipt of the Purchase order.
- (3) Payment schedule : By Demand Draft or cheque after satisfactory installation & working of the equipment in good condition.
- (4) Taxes/VAT/Other statutory duties should be indicated separately. **Please note that no form "C" or "D" will be issued by this station.**
- (5) Liquidated damages for delay 0.5% will be deducted from the bill per week for not undertaking the ordered installation work, within the stipulated time.
- (6) Submission of income tax clearance as issued by Income Tax Department & sales Tax clearance certificate as issued by State / Central Sales tax Department.

Yours faithfully,

  
DIRECTOR I/C

Encls : as above

QUOTATION FOR INSTALLATION OF 1 NO. 30 KVA GENSET AT CSGRC, HOSUR

Sl.No	Description	Unit	Qty	Unit Rate	Amount (Rs.)
1	50 Sqmm, 3 Phase ISI Brand cable and related support materials & work charges	85	mtrs		
2	Exhaust Line : 3 inch x 3.8 mm MS Pipe and related support materials & work charges	10	mtrs		
3	Earthings : ISI Brand GI Pipe of 3.8 mm x 5 feet, salt & charcoal, Covers, Digging and civil work	4	Nos.		
4	Copper strip size : 25 mm x 5 mm with Insulation	10	Mtrs		
5	GI Strip Size 25 x 5 mm with Insulation	10	Mtrs		
6	Busbar Size 18 inch x 18 inch	1	No.		
7	10 Sq. mm cable x 10 Metre & related support materials (for busbar connections)	10	Mtrs		
8	CO2 Fire Extinguisher - 2 Kg	1	No.		
9	Rubber Mat Size 1 Metre x 2 Metre x 10 mm	1	No.		
10	Fire Stand with 2 No. Buckets	2	No.		
11	Labour charges for all the above works				
	<b>Total Installation charges (1 to 11)</b>				

Please Note : Safety Certificate Approval Fee and Service charges are to be mentioned separately.

  
 निदेशक, के.रे.ज.सं.के., होसूर  
 DIRECTOR, C.S.G.R.C., HOSUR